



(HAE-027144) AGREEMENTS REGARDING MOBILE UNITS, CONTAINERS AND (SMOKING) TENTS

RHDHV replaced by Facility Services

Procedure chain (units, containers and smoking tents)

Siting of units/containers:

Locations for units/containers on the YARA site are only to be decided after consulting Facility Services.

At the designated locations for the units/containers, the contractor himself is responsible for order and tidiness (storage of materials, clearing up waste, etc.).

During projects, Yara Sluiskil B.V. may opt to provide smoking areas in the form of tents.

General conditions for arrangement:

The following general conditions are to be satisfied when arranging units and containers.

- In principle, units must be placed as far as possible in accordance with the guidelines given in the document ‘siting of temporary units within 10⁻⁴ contour’



Plaatsen tijdelijke
units binnen 10⁻⁴ con



Risicocontouren.pdf

- Units/containers must satisfy the legal requirements applicable to buildings of this type.
- Units/containers must be inspected and approved before delivery.
- Units/containers must not be placed under electrical circuits or pipe bridges.
- Units/containers must not be placed above wells.
- Units/containers must not block access to:
 - Other buildings
 - Evacuation routes

Document owner:

Erik van der Peijl

Document ID:

YMS0-180-1576

Changes in this version:

<Data required>

Approved by:

Denis Barthouet

Version: 4.0

Approval date:

2018-11-15

A paper copy is an uncontrolled copy of the document

Next review date:

2019-12-02

- Block valves
- Fire prevention systems
- Minimum distance between individual units/containers must be 2 metres.
 - Distance from a hydrant must be at least 3 metres.
 - Distance from a railway track must be at least 3 metres.
- Units/containers must be fitted with safety glass or sheeting.
- Smoking in units/containers/smoking tents is only allowed if this is expressly indicated.
- Smoking units/containers/tents are only to be placed at the designated locations in accordance with the appended drawing.
- Other places in consultation with the QWC&E Department.
- Units/containers are to be equipped with one or more properly working fire extinguishers and flame-extinguishing waste bins.



ROOK KEET
REV.1.pdf

Electricity:

- Units/containers must be equipped with adequate lighting (at least 300 Lux at desk height).
- The electrical system must be capable of being switched off by means of a main switch on each floor.
- *This must be clearly marked and installed in an easily visible and accessible place, preferably next to the main entrance of the units/containers.*
- The electrical system must conform to standards NEN 1010 and NEN 3140.
- Units and containers must be furnished with approval stickers.
- YARA has the right to reject systems that fail to meet the stated requirements, without the owner/company having any claim to any compensation or recompense from YARA.
- Units and containers must be connected up by the in-house, unit-rate electrical contractor.
- Units and containers must be properly earthed.

Heating:

Only electric heating is permitted. The elements must be enclosed. These elements should be attached to a wall.

Clothes must not be hung to dry above the heaters.

Steel containers:

The following additional provisions apply to steel containers fitted out as warehouse or work space:

- The system must be fitted with an earth leak circuit breaker (0.3 A) + 1 main switch.
- No live cables are to be brought outside through the open doors.
- If it is necessary to pass cable through, this should be done through the holes/recesses in the side walls.

Depositing and removing units/containers, and repairs:

- The driver must first report to the Security Officer
- The driver must then report to Facility Services, who will direct him to the department and places where the units/containers are to be deposited or taken away.
- All waybills and repair slips must be signed by Facility Services and must be deposited with them.
- The driver must then report to the department for which he is to deposit/take away units/containers, or carry out a repair (work permit).
- Contractors on the YARA site who wish to deposit/remove units/containers may only do so in consultation with Facility Services.